BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of the Work : Providing Compound wall and other Works to Indira Canteen near Ward Office, HMT Layout 1st Block, 2nd Main Somanna Garden in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
1	115.97	Earthwork **excavation by manual means in ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	38.08	Rupees Thirty Eight And Paise Eight Only
2	8.91	Providing and **Filling in foundation with granite / trap broken metal** 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. etc complete as per specifications and directions of engineer in charge of the work	Cum	2315.52	Rupees Two Thousand Three Hundred Fifteen And Paise Fifty Two Only
3	27.50	Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation** including cost of all materials, labour, HOM of machinery, curing cetc complete as per specifications and directions of engineer in charge of the work	Cum	5449.68	Rupees Five Thousand Four Hundred Forty Nine And Paise Sixty Eight Only
4	10.35	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6, stone** hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4521.96	Rupees Four Thousand Five Hundred Twenty One And Paise Ninety Six Only
5	9.45	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5405.40	Rupees Five Thousand Four Hundred Five And Paise Forty Only
6	29.70	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	105.84	Rupees One Hundred Five And Paise Eighty Four Only
7	1.98	Providing and laying in position **plain cement concrete of mix 1:2:4** with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation, plinth and cills**, ncluding cost of all materials, labour, HOM of	Cum	5876.28	Rupees Five Thousand Eight Hundred Seventy Six And Paise Twenty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
8	46.00	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding,	Sqm	979.56	Rupees Nine Hundred Seventy Nine And Paise Fifty Six Only
9	96.60	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	213.84	Rupees Two Hundred Thirteen And Paise Eighty Four Only
10	82.80	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, with primer etc complete as per specifications and	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only
11	9.25	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided	Sqm	3168.72	Rupees Three Thousand One Hundred Sixty Eight And Paise Seventy Two Only
12	48.00	Sand filling in wells complete as per drawing and technical specifications MORTH etc complete as per specifications and directions of engineer in charge of the work	Cum	6217.56	Rupees Six Thousand Two Hundred Seventeen And Paise Fifty Six Only
13	153.65	Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed , including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	3413.88	Rupees Three Thousand Four Hundred Thirteen And Paise Eighty Eight Only
14	56	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc complete	No	338.04	Rupees Three Hundred Thirty Eight And Paise Four Only
15	8.75	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	28.08	Rupees Twenty Eight And Paise Eight Only
16	8.75	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, etc complete as per specifications and directions of	Sqm	71.28	Rupees Seventy One And Paise Twenty Eight Only
17	4.97	Providing and laying **cement concrete** using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete **(RMC) M 20** for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, **for raft foundation column footing , main and secondary beams** with all lead and lifts etc., complete (exclusive of cost of steel and fabrication	Cum	6349.32	Rupees Six Thousand Three Hundred Forty Nine And Paise Thirty Two Only
18	0.45	Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM	Tonne	60534.00	Rupees Sixty Thousand Five Hundred Thirty Four Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

27/09

Executive Engineer
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

27/09

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
19	28.78	Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for **vertical surface such as walls at any thickness**, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	316.44	Rupees Three Hundred Sixteen And Paise Forty Four Only
20	357.00	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery etc complete	Kgs	84.24	Rupees Eighty Four And Paise Twenty Four Only

I am prepared to execute the above mentioned work written by me in Schedule - B

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor Signature
Reg. No.
Postal Address

27/09

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

27/09